



Clark Regional Wastewater District

Ten-Year Capital Program Capital Project Profile

NE 179th Street Trunk

Location: Central

Number: TBD

GL Number: TBD

Phase: Planning

Project Manager: Les MacDonald

GSP Basin: Whipple Creek East - 2-1605

Capital Improvement Project ☒

General Facilities ☐

District Installed Infrastructure ☐

Septic Elimination Program ☐

Developer Reimbursement Program ☒

Fleet & Facilities ☐

Restoration & Replacement Project ☐

Restoration & Replacement - Gravity ☐

Restoration & Replacement – PS & FM ☐

Restoration & Replacement – Fleet & Facilities ☐

Project Definition:

Background. The District's 2017 General Sewer Plan identifies a gravity sewer and pressure sewer to be installed in NE 179th Street. The District is completing a developer installation of the trunk line east of the NE 29th Avenue intersection in conjunction with Clark County's NE 179th Street and NE 29th Avenue Intersection Improvement Project.

Objective. Extend sewer service in support of development along the NE 179th Street corridor.

Scope of Work. Install 770 feet of 10-inch gravity sewer, 650 feet of 8-inch gravity sewer, and 690 feet of 6-inch force main to accommodate development along the NE 179th Street corridor.

Project Statistics. Gravity Sewer – 1,300 feet of 12-inch and 750 feet of 15-inch gravity sewer.

Photos: (on the reverse side)

Budget Information:

Project Cost Estimate:

Total Project Cost:	\$850,000
Construction Cost:	\$850,000
Basis of Estimate:	
Date of Estimate:	Sept. 2023

Schedule Information:

Activity

Year

Predesign	By Others
Permitting	By Others
Real Property/ROW	By Others
Design	2023-2024
Bid	By Others
Construction	2024

