



Pleasant Valley North Pump Station C (CIP 2-1502C)

Location: Central

Number: TBD

GL Number: TBD

Phase: Design

Project Manager: Les MacDonald

GSP Basin: Pleasant Valley North – 2-1502

Capital Improvement Project ☒

General Facilities ☐

District Installed Infrastructure ☐

Septic Elimination Program ☐

Developer Reimbursement Program ☒

Fleet & Facilities ☐

Restoration & Replacement Project ☐

Restoration & Replacement - Gravity ☐

Restoration & Replacement – PS & FM ☐

Restoration & Replacement – Fleet & Facilities ☐

Project Definition:

Background. Identified in 2017 General Sewer Plan.

Objective. Serve the northeastern portion of Pleasant Valley North Mini-Basin.

Scope of Work. Install a new pump station in the vicinity of NE 50th Avenue and NE 174th Street. Install a force main in a northerly direction along NE 50th Avenue to NE 179th Street.

Project Statistics. Force main – 2,500 feet of 6-inch force main.

Pump station – new submersible pump station with a build out capacity of 285 gpm; three phase electrical service; diesel generator; control kiosk.

Photos: (Map of area on the reverse side)

Budget Information:

Project Cost Estimate:

Total Project Cost:	\$1,530,000
Construction Cost:	\$1,330,000
Basis of Estimate:	Design
Date of Estimate:	Sept. 2023

Schedule Information:

Activity

Year

Predesign	By Others
Permitting	By Others
Real Property/ROW	By Others
Design	2023 - 2024
Bid	By Others
Construction	2025

